

Renovation of reinforced concrete sewer - relining method



Uponor participace

- ✓ Weholite pipes SN8 dn800 -1000 mm - 1419 m. VipLiner modules SN8 dn560 mm - 216 pcs.

Renovation of reinforced concrete sewer - relining method

Renovation of 1.5-kilometer section of reinforced concrete sewer was carried out in 2013 in Chełm.

In early 2013, the Municipal Services Office in Chełm launched a sweeping renovation project of the city's water supply and sewage network. Worth 24 million euros and partly financed from the EU's Cohesion Fund, the project is set to solve a number of problems that have been plaguing the city's water supply and wastewater treatment system for some time.

Projektová fakta:

Location

Chełm, Poland

Dokončení

2013

Typ budovy

Veřejné budovy

Product systems

Obecní kanalizace, Dešťová voda

Typ projektu

Renovation

Partneři

Investor:

Miejskie Przedsiębiorstwo

Gospodarki Komunalnej Sp. z o.o. in

Chełm

Contacto:

Przedsiębiorstwo Bezwykopowej

Renowacji Sieci Podziemnych Sp. z

o.o. in Kielce

The main tasks include expanding the existing water supply and sewage networks to cover the greater Chełm area, and the modernisation of the Bielawin wastewater treatment plant. The project also called for the renovation of a 1.5 kilometre section of an old sewage pipeline passing between Lubelska Street and the Bielawin treatment plant.

Work on-site began in January 2013, with the construction of temporary working chambers and the hydrodynamic cleaning of the old concrete channel. Next, the new PEHD pipes were laid out at surface level, welded together into longer sections and pulled into the host pipeline. The pipes were manufactured and delivered in 12.5 metre sections and welded into sections ranging from 20 to 150 metres in length. The welding was carried out by welders from PBRSP Sp. z o.o., who had been trained beforehand by Uponor Infra service staff. Uponor Infra also lent out a welding machine for large-diameter piping. After a considerable section of the pipeline had been installed, bottoms were crafted by slicing off the top portion of the piping at selected intervals. The annular space between the host pipe and the new liner was filled with specially formulated, impact-resistant grout able to withstand in excess of 5 MPa. In all, between February and August 2013 Uponor Infra delivered 1,419 metres of Weholite DN 800–1,000 pipes to the installation site. An additional 216 pieces of short VipLiner DN 560 modules in 0.5-metre sections were delivered for the renovation of the pipeline at the river crossing.

The renovation provided for a leak-proof and reinforced channel structure. Resistance to wastewater flow has been minimised and the network's parameters have considerably improved. The pipeline is once again fully operational, with its life-cycle extended by at least several decades.

Renovation of reinforced concrete sewer - relining method





+GF+

Kontaktujte nás

Uponor, s.r.o.
Zelený pruh 95/97
140 00 Praha 4 - Braník
Česká republika

Telefon +420 233 313 844
E-mail
zakaznickyservis.cz.sk.bfs@georgfischer.com
W www.uponor.com