References

Park Valley Assisted Living



Uponor involvement

Project highlights

- 21,019 feet of Uponor AquaPEX® pipe in sizes from ½" to 3"
- Application: Overhead in hangers with hot-water recirculation
- Project: 90,000-square-foot senior community
- Special features: Vibrant outdoor and indoor living spaces
- Plumbing installation: A hybrid system using both PEX-a and CPVC

Products used

- Uponor AquaPEX pipe
- ProPEX fittings

A faster install for overhead plumbing application

A luxurious 90,000-square-foot senior community switches from CPVC to Uponor PEX-a to help facilitate a faster install for an...

A 90,000-square-foot senior community featuring 102 assisted living units is completed in Austin, Texas. The facility includes outdoor spaces and courtyards, a salon and spa, exercise room with classes, neighborhood bistro, country store and a playground for children. The project features luxurious accommodations in small and large living suites, one- and two-bedroom units, emergency call systems and large, walk-in closets.

Project Facts:

Location	Completion
US - Southwest, Texas	2016
Vertical markets	Application categories
Multifamily, Healthcare	Plumbing
Project Type	
New building	

90,000-square-foot senior community switches from CPVC to Uponor PEX-a

Project benefits moving from CPVC to Uponor PEX-a

Precision Commercial Plumbing in Pflugerville handled the plumbing installation for this project and they chose Uponor PEX-a as one of the plumbing materials for the job. "It was decided that we use a hybrid system for the domestic water," Richie Blevins, owner of Precision Commercial Plumbing said, "so there is a mix of Uponor PEX-a and CPVC throughout the building." The project, under tight construction timelines, was initially an all-CPVC project, but Blevins quickly realized that in order to keep the project at its fast-pace schedule, he needed Uponor's PEX-a to speed up installation time. "The construction company, Rogers O'Brien Construction, wasn't too familiar with PEX-a piping, so it took a bit of time to show them its effectiveness and ease in installation," Blevins said.

Precision Commercial Plumbing had only completed one previous Uponor PEX-a plumbing installation prior to the Park Valley Assisted project. "I was so impressed with the flexibility of PEX-a on the original job, and I really didn't know how much quicker it installs until I saw it for myself," Blevins said.

With each installation comes additional experience, and Blevins says that he and his guys learned a lot on the job. "We struggled a little in areas where pipe had to be hung with hangers. It was more cumbersome than we had anticipated and it slowed us down a little, but even with these difficulties, it was way faster to install than any other product I've worked with."

And the Precision plumbing installers who worked the Austin project are eager to get to the next project. "Our guys had only positive things to say about working with the flexibility of PEX tubing and we're even becoming comfortable using new terminology such as 'pulling pipe' and 'ring fittings,'" he jokes. "All in all, it was a great learning experience, and we will definitely continue to use PEX in future projects."

Park Valley Assisted Living



> It was a great learning experience, and we will definitely continue to use PEX in future projects.

Uponor Canada

Uponor Ltd.
6510 Kennedy Road
Mississauga, ON L5T 2X4

General: 888.994.7726
Fax: 800.638.9517

W www.uponor.com