

Pre-insulated Wirsbo hePEX coils

Project information	
Job name:	Location:
Engineer:	Date submitted:
Contractor:	Submitted by:
Manufacturer's representative:	Approved by:

Technical data	
Material	PEX
Temp/pressure ratings	73 °F (23 °C) at 160 psi (11 bar)
	180 °F (82 °C) at 100 psi (6.9 bar)
	200 °F (93 °C) at 80 psi (5.5 bar)
Product information and application use	

Pre-insulated Wirsbo hePEX™ complies with the most recent versions of ASHRAE 90.1 and the International Energy Conservation Code (IECC). The product is available with ½" to 1½" oxygen-barrier PEX-a service pipe covered in ½" to 1½" insulation. The insulation features manufactured-sealed seams running the entire length of the pipe for added convenience and system performance. Check with local code authorities regarding energy-code requirements for specific applications.



Note: Temperature and pressure ratings stated are hydrostatic ratings. For domestic hot-water (DHW) and DHW recirculation installations, operating conditions should not exceed 140°F (60°C) at 80 psi (5.5 bar) in accordance with ASTM F2023. For additional information regarding application-specific temperature and pressure ratings, refer to the Uponor PEX Piping Systems Design and Installation Manual.

Part name	Part no.	Inner diameter coil [inch]	Outer diameter coil [inch]	Coil width [inch]	Inner diameter pipe [inch]	Outer diameter pipe [inch]	R value	Weight per UOM [lbs/UOM]
1/2" Pre-insulated Wirsbo hePEX with 1/2" insulation, 100-ft. coil	A6140500	19	30	8.5	0.475	0.625	3.9	8
3/4" Pre-insulated Wirsbo hePEX with 1/2" insulation, 100-ft. coil	A6140750	19	32	12.5	0.671	0.875	3.6	12.8
1" Pre-insulated Wirsbo hePEX with 1/2" insulation, 100-ft. coil	A6141000	19	31	12.5	0.862	1.125	3.4	21
3/4" Pre-insulated Wirsbo hePEX with 1" insulation, 100-ft. coil	A6150750	19	39	12.5	0.671	0.875	7.9	22
1" Pre-insulated Wirsbo hePEX with 1" insulation, 100-ft. coil	A6151000	19	40	14	0.862	1.125	6.4	30.2
1 1/4" Pre-insulated Wirsbo hePEX with 1" insulation, 100-ft. coil	A6151250	27	40.5	12	1.054	1.375	6.1	39.2
3/4" Pre-insulated Wirsbo hePEX with 1 1/2" insulation, 100-ft. coil	A6160750	27	46.5	12	0.671	0.875	10.3	29
1" Pre-insulated Wirsbo hePEX with 1 1/2" insulation, 100-ft. coil	A6161000	27	49.5	12	0.862	1.125	9.57	37.5
1 1/4" Pre-insulated Wirsbo hePEX with 1 1/2" insulation, 100-ft. coil	A6161250	27	52.5	12	1.054	1.375	9.04	46.3
1 1/2" Pre-insulated Wirsbo hePEX with 1 1/2" insulation, 75-ft. coil	A6161500	27	55.5	12	1.244	1.625	11.2	49.5

Part name	Part no.	Codes	Standards	Listings
Pre-insulated Wirsbo hePEX coils	All	IMC UPC IBC IRC NBC of Canada IPC UFGS NPC of Canada UMC NSPC	ASTM F1960 ASTM F876 ASTM F2023 ASTM E814 ULC S115 ASTM F877 CSA B137.5 CSA B214 NSF/ANSI/CAN 61 ULC S101 NSF/ANSI 14	IAPMO-ES ICC-ES-PMG cNSFus-rfh cNSFus-pw CCMC PPI TR-4 CSA UL U.P.Code cQAlus P321

Installation	Related applications
Use ProPEX® fittings to connect the piping. Refer to the ProPEX Connections Instructional Guide or the Uponor Radiant Floor Heating Installation Handbook for additional information.	Pre-Insulated Pipe Systems
	Radiant Heating and Cooling Systems
	Hydronic heating and cooling systems
	Permafrost Protection Systems
	Turf Conditioning Systems

Footnotes		Contact information	
-		Uponor Inc.	Uponor Ltd.
		5925 148th Street West	6510 Kennedy Road
		Apple Valley, MN 55124	Mississauga, ON L5T 2X4
		T 800.321.4739	T 888.594.7726
		F 952.891.2008	F 800.638.9517